

ITEM 874.3  
ITEM 877.2

TRAFFIC SIGNS REMOVED AND STACKED  
SIGN POST REMOVED AND STACKED

EACH  
EACH

Work under this Item shall include the dismantling, removal, transporting and stacking of the existing roadside traffic signs as indicated on plans or as directed by the Engineer including the removal and disposal of the sign supports and their foundations.

The work shall include removing the supports, excavating the existing foundation, the disposal of the concrete and supports, the backfilling with compacted gravel of the holes resulting from the excavation and the removal of the supports and the replacement, in kind, of any surface material disturbed outside of areas to be reconstructed under this project. If in the opinion of the Engineer, the existing foundation will not interfere with new construction, it may be removed to a depth of 6 inches below the existing ground, backfilled with compacted gravel and the existing surfaces restored or replaced in kind.

The signs and posts removed shall be delivered to the Boston Transportation Department, Operations Division - Sign Shop, 12 Channel Street, Suite 105, Boston, MA in the EDIC Industrial Park.

The existing signs shall not be removed until the new signs and structures replacing them are ready for traffic or until the Engineer shall permit.

Payment for work to be done under this Item will be by the each price, which price will be full compensation for dismantling, loading, transporting, and stacking of the signs as designated above. The excavating and disposal of the existing foundation of the same and the supplying and placing of compacted gravel backfill where foundations and posts are removed, restoration of surface, and all other incidentals necessary for the proper completion of this Item.